	202	18 WYLIE SCHOOL HOUSE RENOVATIONS PROJECT LIST		2018 QUOTES		
Priority	ITEM	Comments/notations	2017 cost	Joseph Escher	Four Owls LLC	JXN Renovations
1	Repair wiring	Safely secure wiring to building; check internal wiring, outlets & circuits				
		(offer to do gratis by licensed electrician Kevin Schultz)				
2	Repair woodwork	Cut shrubs back away from building for access & crawl-space ventilation	N/A			
		Replace two front entry thresh-holds, sills & kickplates with white oak	\$ 1,200.00	\$ 1,200.00		
		Replace bottom window sash, trim sill on 2 nd & 3 rd window on the N side	\$ 750.00	\$ 1,400.00		
		Replace window sill & trim on 3 rd window on S side	\$ 750.00	\$ 400.00		
		Replace bottom clapboard & water board (18 feet from rear corner) and	\$ 200.00	\$ 250.00		
		rotted sill plate on right side				
		Replace 6 feet clapboard rear W wall				
		Caulking around replaced windows and doors	\$ 15.00	\$ 150.00		
		Replace right side interior corner floor board (approximately 12') and wall				
		board				
		Replace 4 clapboards & bottom water board at the left side front corner to		\$ 250.00		
		door				
		Repair both exterior doors with plywood fitted insert panels over both		\$ 500.00		
		inside and outside weatherproof caulk. Right side door (latch side) interior				
		corner needs 6" replacement.				
		Replace outhouse rotted boards	\$ 250.00	\$ 350.00		
		Prime all repaired/replaced items with one coat exterior latex primer		\$ 450.00		
	TOTAL	(* includes costs for white oak which A. Nieminen has offered to donate)		\$ 4,950.00 *		\$ 7,980 *
3	Repaint entire exterior	Removal of lead base paint			\$ 9,765.00	
		6Mil Containment System			\$ 2,835.00	
		Leads removal supervisor			\$ 5,700.00	
		Labor			\$ 8,400.00	
		Apply primer			\$ 819.00	
		Paint exterior			\$ 1,839.60	
	TOTAL	(** doesn't include painting which Ekonk Grange has volunteered to do)	\$ 14,000.00		\$ 29,358.60	\$ 11,500.00 **
4	Repair chimney &	Repair chimney; replace chimney crown	\$ 550.00			
	stove					
		Repair stove pipe shields & waterproof; repair the pipe damper and the	\$ 1,421.00			
		connection between the vent pipe behind the cement board and the				
		chimney; clean the horizontal & vertical sections of the vent pipe				
5	Repair/replace the bell,	Replace the yoke which appears to be in too many cast-iron fragments to				
	yoke and stand	be successfully repaired; assess the bell for repairs or recasting; determine				
		if historical restoration criteria apply (to be examined by Greg Farmer)				

	6	Replace flagpole	May be available through DEEP (as per R. Millovitsch)			
--	---	------------------	---	--	--	--